



REQUEST FOR TENDER

(RFT 2023-01)

Addendum #2

The bid documents shall be amended to include the following, which will become part of the contract documents.

1) Location 3: Sgt. Wilde Rd from 12th St to Manning Ave

- a) Question (Town answers in red):
- Is the level course also type 1 asphalt or could I use type 2 – **either type would be acceptable.**

2) Location 4: WA Day School Parking Lot Reconfiguration

- a) Revised site plan is attached below.
- b) Questions (Town answers in red):
- Where is the curb being installed and what type of curb? – **new curb is adjacent to the 3.0m sidewalk which runs east-west along the centre of the site. Curb type = barrier curb.**
 - Is regular parking lot paint acceptable or are you looking for something more heavy duty like thermoplastic? – **regular street paint is acceptable.**
 - Are the parking stall bumpers rubber or concrete? – **either type is acceptable, preference would be the more economical option.**
 - What is to be included in the line painting? – **line painting is as follows:**
 - all parking stalls (i.e. parallel and angle) shown in white and yellow hatching
 - directional arrows in car parking area. Colour = white.
 - Bus loading area – “bus loading zone” text shown on revised plan. Colour = yellow

20 ST

LANDSCAPE
ROCK AREA

20.00
BUS LOADING
ZONE

POST AND CABLE

20.00
BUS LOADING
ZONE

BARRIER CURB

NEW SIDEWALK

BARRIER CURB

WHEELCHAIR
ACCESS
RAMP

6.70

2.40

3.00

8.00

8.00

6.40

2.60

8.00







LILLIE DAVIS (6th) AVE

WA Day Parking Lot

Lots 6-9, Block 145, Plan 92B & Lots 6-9, Block 149, Plan 92B

Town of Fort Macleod

Conceptual Layout

- Concrete 
- Asphalt Parking Lot (65 Stalls + 4 Handicap) 
- Amenities 
- Existing Title Lines 
- Parent Drop Off 
- Bus Drop Off 
- Stall Bumber 